

Kirkwood Meadows Public Utility District – Wintergreen Sewer Replacement

BID ADDENDUM NO. 2

Specification No.: _____

Date: July 29, 2024

QUESTIONS:

1. “Are there no liquidated damages on the Wintergreen Sewer project, or was it a mistake that this was left blank in section 5.35 on page 298”.

Section 5.35 is amended to read “...the Contractor shall pay to the District as damages the amount of \$1,500 per day...”

2. “Does the District have any property where dirt piles could be stockpiled for the Wintergreen Sewer Project?”

Dirt removed can be spread within the existing easement to a maximum depth of 6” provided it is compacted to 85% and any necessary erosion control measures are implemented to ensure stormwater pollution does not enter Kirkwood Creek. Edges of spoil placement area shall be blended for gradual transition to existing grades. Backfill materials can be temporarily stockpiled within the existing easement, provided they are covered if not in use for more than 2 days.

End of Addendum No. 2